

# PARLIAMENT HOUSE RDC UPGRADE



## PROJECT DETAILS

**PROJECT LOCATION:**  
Parliament House, Parliament  
Dr Canberra ACT 2600

**COMMENCEMENT DATE:**  
-

**COMPLETION DATE:**  
August 2013

**TYPE OF CONTRACT:**  
Construct

**CONTRACT VALUE:**  
\$500,000

**GROSS FLOOR AREA:**  
-

**PROJECT MANAGER:**

**CONSTRUCTION  
MANAGER:**

## OVERVIEW TRADE PACKAGE

- Star Group ACT Division provided electrical services for the Department of Parliamentary Services on the
- Parliament House RCD upgrade project. Star was engaged by the Department of Parliamentary Services (DPS) to undertake the RCD Upgrade Project – Stage 4(Suites) on Parliament House.
- This project involved the upgrade of existing circuit breakers to RCD protected breakers within 158 Members and Senators
- Star provided programme of works, scheduled around labour and availability of access to suites. This programme was continually updated, as access was approved or rejected to particular suites based on availability.

- A night shift was commenced in order to complete works in suites where day access was unavailable.

## PROJECT SPECIFICS

- A photographic dilapidation report was undertaken for each suite prior to commencement of works and comprehensive installation and commissioning checklist was completed for each switchboard. The dilapidation report and all required deliverables were submitted to DPS each week during the six week project.
- Star's proactive engagement with DPS Project Officers resulted in the works being delivered 1.5 months before the original DPS projected completion date.